Figure: 25 TAC §289.229(h)(2)(A)(i)

System	Leakage Limit	Measurement Location
0-150 kVp (manufactured or installed prior to March 1, 1989)	1 R (10 mGy) in 1 hr	1 meter (m) from source
0-150 kVp (manufactured on or after March 1, 1989)	100 mR (1mGy) in 1 hr	1 m from source
151-499 kVp	1 R (10 mGy) in 1 hr	1 m from source